



- DO NOT CUT OR DAMAGE LEADER, PRUNE DAMAGED OR DEAD BRANCHES AFTER PLANTING AND STAKING. KEEP CROWN SHAPE TYPICAL OF SPECIES.
- SPECIFIED TREE STRAP COLLAR, DO NOT TWIST. STAKES TO BE SECURED TO TREE ABOVE THE FIRST LATERAL BRANCHES BUT NO HIGHER THAN HALF OF THE TREE HEIGHT.
- 14 GAUGE GALV. WIRE WITH 1/2" DIA. X 18" WHITE PVC PIPE ON EACH WIRE.
- (3) SPECIFIED POSTS, 2" DIA., 6'-8' HIGH, ALIGN EQUIDISTANT AROUND TREE. KEEP PLUMB WITH TOPS EVEN. DRIVE 12" INTO UNDISTURBED SUBGRADE OUTSIDE PLANTING PIT. TREE STAKES LOCATED INSIDE WATERING SAUCER ON TREES GREATER THAN 3" CALIPER. USE GUYS AS PER DETAIL NO. 1500-8
- WRAP ENTIRE SURFACE OF TRUNK FROM THE BASE UP TO BRANCHES WITH REQUIRED WRAPPING, WHEN SPECIFIED. REFER TO SPECIFICATIONS. SECURE AT TOP WITH DUCT TAPE.
- ROOT FLARE TO BE AT OR SLIGHTLY ABOVE THE FINISHED GRADE. SET TRUNK PLUMB. SEE NOTES AND SPECIFICATIONS IN SECTION 1500.
- APPLY SPECIFIED MULCH AT 0" DEPTH AT TRUNK AND 4" DEPTH AT EDGE OF RING, INSIDE WATERING SAUCER. REMOVE SAUCER UPON SODDING/ SEEDING IN IRRIGATED AREAS.
- FILL DOWNHILL SIDE OF ROOTBALL WITH SPECIFIED BACKFILL MIXTURE. AMENDMENTS AS SPECIFIED IN TOP 12" DEPTH.
- WATER SAUCER AT LOWER HALF OF PLANT PIT, 4" IN HEIGHT OR AS NEEDED.
- REMOVE ALL TWINE AND BURLAP FROM TOP 1/3 OF ROOTBALL. COMPLETELY REMOVE WIRE BASKET.
- INITIAL STABILIZING BACKFILL 1/3 DEPTH, COMPACTED. SEE NOTES SPECIFICATIONS IN SECTION 1500.
- UNDISTURBED PIT BOTTOM FOR ROOTBALL BASE.

NOTES

1. THIS INSTALLATION SHALL APPLY TO ALL TREE TYPES AND SIZES PLANTED ON SLOPES 3:1 OR GREATER.
2. GUYING AND STAKING TO BE REMOVED AFTER ONE GROWING SEASON.
3. DO NOT PLANT ANY PLANT WITH A ROOTBALL THAT IS NOT IN COMPLIANCE WITH THE COLORADO NURSERY ACT REQUIREMENTS.

DECIDUOUS TREE PLANTING ON SLOPE

NTS

